

ADDENDUM #1

15. Scope of Work

- 15.1** Approximate Scale Capacity - 110,000 kgs
- 15.2** CLC rating 80,000 lbs
- 15.3** Minimum deck plate thickness of 3/8 inches
- 15.4** Stainless steel load cells
- 15.5** Junction Boxes to be of stainless-steel construction
- 15.6** Include Guard Rails
- 15.7** Scale Width to be 10 feet
- 15.8** Pictou County Solid Waste Management will provide Crane to remove and install scales.
- 15.9** Pictou County Solid Waste Management will coordinate logistics of placement of old scales.
- 15.10** Site visit is recommended to establish current equipment and requirement for new equipment to ensure proper communication between scales and computer system, i.e. requirement / options for new indicator.
- 15.11** Traffic volume fluctuates between 150 to 300 vehicles per day.
- 15.12** Steel and Concrete platform proposals will be accepted.
- 15.13** Foundation Drawing available upon request.